



Key

- Existing road markings
- New road markings
- New road sign on single post
- New fixed concrete bollard
- New blank faced reflective bollard
- Half Battered kerb and quadrants with 120mm as per BCC SD HW/11.01.
- Full depth flexible footway construction as per BCC SD HW/11.15 & BCC SD HW/11.56

Notes:

- All sign faces, posts, planters and concrete blocks will be removed for re-use or storage.
- Changes to traffic regulation orders will be subject to statutory consultation.

<p>Birmingham City Council TRANSPORT AND CONNECTIVITY 1 LANCASTER CIRCUS, BIRMINGHAM, B4 7DQ</p>	SCHEME							
	Kings Heath and Moseley PTP Package 2							
<p>Proposed traffic calming Springfield Road</p>	DRAWING		DATE	REV.	REVISIONS		DRN	PM
	14/02/26		AJT	25/01/24	AB	25/01/24	CM	25/01/24
		DRAWING STATUS				SCALE		
		GENERAL				N.T.S		
		DWG. No						
		L00228 S1 027						